

TABLE OF QUANTITIES

TYPE	L	CONCRETE				REINFORCING STEEL															
		Type I	Type II	BARS A	BARS B	BARS E	BARS H	BARS U-1	BARS U-2	BARS V	BARS V-1	BARS V-2	BARS V-3	TYPE I	TYPE II						
		FT. CU. YD.	CU. YD.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	NO. LN.*FT.	Lbs.	Lbs.					
DI-14A	3'	2.23	2.20	3 4'-0"	5 4'-0"	-	-	38 4'-0"	-	-	-	-	48 3'-4"	12 2'-6"	3 3'-8"	8 5'-9"	455	455			
DI-14B	4'	2.45	2.44	3 5'-0"	5 5'-0"	8 1'-4"	38 4'-0"	2 5'-2" TO 5'-8"	2 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	4 3'-8"	8 5'-9"	485	480						
	6'	2.91	2.89	3 7'-0"	5 7'-0"	8 3'-4"	38 4'-0"	4 5'-2" TO 5'-8"	4 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	5 3'-8"	8 5'-9"	528	519						
	8'	3.36	3.34	3 9'-0"	5 9'-0"	8 5'-4"	38 4'-0"	6 5'-2" TO 5'-8"	6 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	7 3'-8"	8 5'-9"	573	560						
	10'	3.82	3.78	3 11'-0"	5 11'-0"	8 7'-4"	38 4'-0"	8 5'-2" TO 5'-8"	8 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	8 3'-8"	8 5'-9"	617	600						
	12'	4.28	4.24	3 13'-0"	5 13'-0"	8 9'-4"	38 4'-0"	10 5'-2" TO 5'-8"	10 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	9 3'-8"	8 5'-9"	660	639						
	14'	4.74	4.69	3 15'-0"	5 15'-0"	8 11'-4"	38 4'-0"	12 5'-2" TO 5'-8"	12 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	11 3'-8"	8 5'-9"	706	679						
	16'	5.20	5.14	3 17'-0"	5 17'-0"	8 13'-4"	38 4'-0"	14 5'-2" TO 5'-8"	14 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	12 3'-8"	8 5'-9"	749	719						
	18'	5.67	5.61	3 19'-0"	5 19'-0"	8 15'-4"	38 4'-0"	16 5'-2" TO 5'-8"	16 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	13 3'-8"	8 5'-9"	793	758						
	20'	6.13	6.06	3 21'-0"	5 21'-0"	8 17'-4"	38 4'-0"	18 5'-2" TO 5'-8"	18 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	15 3'-8"	8 5'-9"	838	799						
DI-14C	6'	2.91	2.89	3 7'-0"	5 7'-0"	16 2'-0"	38 4'-0"	6 5'-2" TO 5'-8"	6 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	5 3'-8"	8 5'-9"	543	530						
	8'	3.36	3.34	3 9'-0"	5 9'-0"	16 3'-0"	38 4'-0"	8 5'-2" TO 5'-8"	8 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	7 3'-8"	8 5'-9"	588	571						
	10'	3.82	3.79	3 11'-0"	5 11'-0"	16 4'-0"	38 4'-0"	10 5'-2" TO 5'-8"	10 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	8 3'-8"	8 5'-9"	632	610						
	12'	4.28	4.24	3 13'-0"	5 13'-0"	16 5'-0"	38 4'-0"	12 5'-2" TO 5'-8"	12 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	9 3'-8"	8 5'-9"	675	646						
	14'	4.74	4.69	3 15'-0"	5 15'-0"	16 6'-0"	38 4'-0"	14 5'-2" TO 5'-8"	14 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	11 3'-8"	8 5'-9"	720	690						
	16'	5.20	5.14	3 17'-0"	5 17'-0"	16 7'-0"	38 4'-0"	16 5'-2" TO 5'-8"	16 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	12 3'-8"	8 5'-9"	764	729						
	18'	5.67	5.61	3 19'-0"	5 19'-0"	16 8'-0"	38 4'-0"	18 5'-2" TO 5'-8"	18 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	13 3'-8"	8 5'-9"	807	768						
	20'	6.13	6.06	3 21'-0"	5 21'-0"	16 9'-0"	38 4'-0"	20 5'-2" TO 5'-8"	20 3'-1" TO 3'-7"	48 3'-4"	12 2'-6"	15 3'-8"	8 5'-9"	853	809						

NOTES

- DEPTH OF INLET (H) TO BE SHOWN ON PLANS.
- THE "H" DIMENSION SHOWN ON THE STANDARDS AND SPECIFIED ON THE PLANS WILL BE MEASURED FROM THE INVERT OF THE OUTFALL PIPE TO THE TOP OF THE STRUCTURE. PLAN "H" DIMENSIONS ARE APPROXIMATE ONLY FOR ESTIMATING PURPOSES AND THE ACTUAL DIMENSIONS SHALL BE DETERMINED BY THE CONTRACTOR FROM FIELD CONDITIONS.
- WHEN SPECIFIED ON THE PLANS THE INVERT IS TO BE SHAPED IN ACCORDANCE WITH STANDARD IS-1. THE COST OF FURNISHING AND PLACING ALL MATERIALS INCIDENTAL TO THE SHAPING IS TO BE INCLUDED IN THE BID PRICE FOR THE STRUCTURE.
- IN THE EVENT THE INVERT OF THE OUTFALL PIPE IS HIGHER THAN THE BOTTOM OF THE STRUCTURE, THE INVERT OF THE STRUCTURE SHALL BE SHAPED WITH CEMENT MORTAR TO PREVENT STANDING OR PONDING OF WATER IN THE STRUCTURE. THE COST OF FURNISHING AND PLACING ALL MATERIALS INCIDENTAL TO THE SHAPING IS TO BE INCLUDED IN THE BID PRICE FOR THE STRUCTURE.
- STEPS ARE TO BE PROVIDED WHEN H IS 4'-0" OR GREATER. FOR DETAILS SEE STANDARD ST-1.
- THIS ITEM MAY BE PRECAST OR CAST-IN-PLACE.
- 3" DIAMETER WEEP HOLE TO BE LOCATED TO DRAIN SUBBASE MATERIAL. WEEP HOLE WITH 12"X12" PLASTIC HARDWARE CLOTH 1/4" MESH OR GALVANIZED STEEL WIRE, MINIMUM WIRE DIAMETER 0.03", NUMBER 4 MESH HARDWARE CLOTH ANCHORED FIRMLY TO THE OUTSIDE OF THE STRUCTURE.
- ALL REINFORCING STEEL SHALL HAVE A MIN. COVER OF 2".
- ALL REINFORCING STEEL TO BE CUT CLEAR OF ALL OPENINGS BY 2".
- CAST-IN PLACE CONCRETE IS TO BE CLASS A3 (3000 PSI). PRECAST CONCRETE IS TO BE 4000 PSI.
- LENGTH OF SLOT (L) WILL, IN EVERY CASE, BE SHOWN ON PLANS.
- CONCRETE QUANTITIES SHOWN ARE FOR DEPTH (H) OF 3'-0" WITHOUT PIPES. THE AMOUNT DISPLACED BY PIPES MUST BE DEDUCTED TO OBTAIN TRUE QUANTITIES. FOR INLETS OF DIFFERENT DEPTHS ADD OR SUBTRACT 0.36 CUBIC YARDS OF CONCRETE FOR EACH FOOT OF DEPTH. AND 84 LBS. OF REINFORCING STEEL.
- LENGTH OF ANGLE IRON AS SHOWN ON SHEET 1 OF 2 IS TO BE L +16" AT 4.10 LBS./FT..
- * DENOTES LENGTH OF ONE (1) BAR.
- GRATE TO BE INSTALLED SO SLOTS WILL DIRECT WATER TOWARD THE INLET THROAT. GRATE MUST BE REVERSIBLE (RIGHT HAND GRATE IS SHOWN).
- PROVIDE SAFETY SLABS WHEN SPECIFIED ON THE PLANS.
- FOR DETAILS AND DIMENSIONS NOT SHOWN FOR MEDIAN BARRIER SEE STANDARD MB-12.
- QUANTITIES INCLUDE MB-12.

CONCRETE MEDIAN BARRIER DROP INLET
12"-36" PIPE: DEPTH (H) = 20'-0" MAX.

VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION
REFERENCE

233
302